

Architectural Guide Specifications for Kinetex

SPECIFICATION DIVISION 09 - INTERIOR FINISHES

SECTION 096813 - MODULAR FLOORING FOR COMMERCIAL APPLICATION

Revised: Ocotober 2025

J+J Flooring, P. O. Box 1287, Dalton, Georgia 30722

Be sure to obtain the latest version of this specification. Edit suggested guide specifications in accordance with project requirements. Delete, add, or modify text as required. You are responsible for the accuracy for of all project specifications. NEITHER KINETEX NOR J+J Flooring SHALL BE LIABLE FOR ANY DAMAGES ARISING OUT OF THE USE OF ANY OF ITS GUIDE SPECIFICATIONS.

Copyright: 2026 by J+J Flooring. Limited permission is hereby granted to incorporate portions of this guide specification into project specifications requiring the use of Kinetex textile composite flooring.

SECTION 096813

PART 1 GENERAL

1.01 THIS SECTION INCLUDES

A. Textile composite flooring modules as shown on the drawings and schedules and as indicated by the requirements of this section.

1.02 RELATED DOCUMENTS

A. Drawings and General Provisions of the Contract (including General and Supplementary Conditions and Division 1 sections) apply to the work in this section only.

1.03 RELATED SECTIONS

- A. Other Division 9 sections for floor finishes related to this section but not the work of this section.
- B. Division 3 Concrete - not included work this section.
- C. Division 6 Wood and Plastics - not included work this section.
- D. Division 7 Thermal and Moisture Protection - not included work this section.

1.04 QUALITY ASSURANCE AND REGULATORY REQUIREMENTS

A. Qualifications of flooring installation contractor: All work shall be done by installation firms specializing in commercial flooring and carpet installation. It is required, that the firm or individual shall be a member of the Floor Covering Installation Contractors Association (FCICA) and/or certified by the Certified Floorcovering Installers Association (CFI). Flooring contractor to be specialty contractor normally engaged in this type of work and shall have three (3) years minimum documented experience in commercial installation of similar flooring materials and participation in manufacturer's environmental program including responsible flooring removal, recycling, and installation.

- B. Flooring contractor will be responsible for the proper product installation, including floor preparation in all the areas indicated in the drawings to receive Kinetex modules. The installation standard will be as listed in J+J Flooring Kinetex Installation Instructions.
- C. Flooring contractor to provide owner a written warranty that guarantees the completed installation to be free from defects in materials and workmanship for a period of no less than two (2) years after job completion.
- D. Manufacturer qualifications: Manufacturing facility to ISO 14001 certified and have a minimum of 20 years experience in the manufacture of commercial flooring.
- E. Manufacturer to offer a reclamation program for the recycling of existing broadloom carpet, modular carpet tile and textile composite flooring.
- F. All warranties must be issued by the manufacturer as standard published warranties on all types of flooring modules within this document. Second source warranties that involve parties other than the textile composite flooring manufacturer are unacceptable. If the product fails to perform as warranted when installed according to the J+J Flooring's Kinetex installation instruction and maintained according to J+J Flooring's Kinetex maintenance instructions, the affected area will be repaired or replaced at the expense of the manufacturer. J+J Flooring will provide standard published written performance warranties for the following:
1. Lifetime product performance. Will not delaminate along seams or lose more than five (5%) percent by weight of fiber during its useful life.
 2. Lifetime static propensity, meaning built-in protection below 3.0 kv as tested under AATCC-134.
 3. Lifetime Stain Removal
 4. Lifetime Colorfastness (Light and Crocking)
- G. Manufacturer to provide field service experts to assist in project start-up as required by the job and will notify owner, architect, general contractor, or another designated contact if any installation instructions are not followed.
- H. Provide flooring material to meet the following test performance criteria as tested by a recognized independent testing laboratory. Certified test reports shall be submitted by the manufacturer for each test method. Requirements listed below must be met by all products being submitted for approval:
1. Pill Test / DOC-FF-1-70 (ASTM D-2859) - Requirement: Pass
 2. Flooring Radiant Panel / ASTM E-648 - Requirement: Class I (Above .45 w/cm)
 3. CRI VOC Chamber Test/Indoor Air Quality test (CRI-IAQ) Green Label Plus™ Test.
 4. Lightfastness: Rating of not less than 5 on International Grey Scale after 40 SFU's when tested in accordance with AATCC Test Method 16.3.
 5. Crockfastness: Minimum stain rating on International Grey Scale of not less than 5 wet or dry when tested in accordance with AATCC Test Method 165.
 6. Atmospheric Fading: Burned Gas shall not be less than 5 on International Grey Scale after two cycles on each test as per AATCC Test Method 129 Ozone and AATCC Test Method 23.
 7. Noise Reduction Coefficient (ASTM C 423-02): NRC Rating of 0.30
 8. Impact Insulation Classification (ASTM E 492-09): IIC Rating of 64
 9. Slip Resistance (ASTM 1028-96): Complies with ADA Guidelines for level surface
 10. Thermal Insulation (ASTM C 518): R. 73

1.05 SUBMITTALS

- A. Submit to architect and/or owner ten (10) days prior to bid, two (2) 6.5" x 6.5" (minimum size)

finished samples of the exact type of flooring proposed, including quality, pattern, color and backing.

B. Submit to architect and/or owner ten (10) days before bid, any proposed substitutions for consideration. Submit at least three (3) references of installations using the same flooring technology, as described within this text. Include contact names and telephone numbers.

C. Submit manufacturer's warranties, installation instructions, and maintenance instructions before bid date.

D. Submit the manufacturer's certification that the flooring has been tested by an independent laboratory and complies with the required flammability tests as well as other testing requirements as listed under 1.04 F.

1.06 ENVIRONMENTAL/FIELD CONDITIONS

A. Deliver all materials to the installation site in the manufacturer's original packaging and in good condition. Packaging to contain manufacturer's name and marks, identification number, shipping and handling instructions and related information.

B. Delivered and stored materials must be available for inspection as required by the owner, architect, general contractor and/or the manufacturer.

C. Sub-floor preparation is to include all required work to prepare the existing floor for installation of the product as specified in this document. Sub-floor preparation shall meet all conditions as specified in J+J Flooring's Kinetex textile composite flooring installation instructions.

D. Sub-floor preparation will include, as required, the removal and repair of the existing floor surface. It is required that the floor of a renovation project be inspected before the bid date.

E. All materials, including adhesives, are to be delivered to the site of installation at a minimum of 48 hours prior to the start of installation and stored in a clean and dry room that measures above 65°F and below 95°F and measures between 10% and 65% relative humidity (RH). To maintain temperature and relative humidity, permanent heating and air conditioning systems (HVAC) must be in operation. Place pallets of textile composite flooring modules on a flat surface (do not double stack pallets). After work is completed, the ambient room temperature should remain at 65°F and relative humidity between 10% and 65% for 48 hours. These materials and related adhesives shall be protected from the direct flow of heat from heating fixtures and appliances such as hot-air registers, radiators, or other. Site conditions shall include those specified in the flooring manufacturer's installation instructions and shall also include sufficient heat, light and power required for effective and efficient working condition.

F. Once the temperature and relative humidity in area for installation have been stabilized, loose lay the modules within the installation area and allow them to precondition for 48 hours prior to installation. Module installation shall not commence until painting and finishing work is complete and ceiling and overhead work is tested, approved and completed. Traffic shall be closed during the installation of the textile composite flooring products. Verify concrete slabs are dry per the standards for bond and moisture tests listed in the manufacturer's installation instructions.

1.07 SUBSTITUTIONS

A. All Bid submittals must conform to the specifications in this document.

B. All test results to be in accordance with a certified independent testing laboratory.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Acceptable Manufacturer: Kinetex, a brand of J+J Flooring, P.O. Box 1287, Dalton, GA, 30722. (800) 241-4586. JJFLOORINGGROUP.COM. Please contact ERICA LOESER, (440) 645-1105, erica.loeser@jjflooringgroup.com

Any alternate manufacturer and/or product must meet or exceed those requirements specified under all sections of this document in pattern, color, and fiber. Any substitutions must be made in accordance with Section 1.00 of this document.

2.02 TEXTILE COMPOSITE FLOORING MATERIALS

A. Kinetex flooring modules (tiles):

1. Product: Tri-Plex II 1852
2. Color: French Hens 2595
3. Backing: Kinetex Felt Cushion
4. Dye Method: Solution Dyed
5. Wear Layer: 100% Polyester
6. Total Weight (Nominal Average): 4.5 oz - 5.2 oz / square foot
7. Pattern Repeat: N/A
8. Soil Release: Yes
9. Standard Size: 24" x 24" (approx. (60.96cm x 60.96 cm)
10. Warranties: Lifetime Product Performance, Colorfastness to Light & Crocking, Stain Removal, Static Protection, Protection from Edge Ravel and Delamination Failure; Lifetime Dimensional Stability.
11. Testing Specifications - Pill Test: Yes
12. Testing Specifications - Flooring Radiant Panel: Class 1
13. Testing Specifications - Smoke Density: Less than 450.0 flaming (ASTM E 662)
14. Testing Specifications - Static Test: Less than 3.0kv (AATCC-134)
15. Recycled content: Minimum of 47% recycled content
16. NSF/ANSI 140 Platinum Certified
17. Closed-loop recyclable

2.03 ADHESIVES

A. Kinetex® Adhesive, an aggressive, pressure-sensitive adhesive designed for the installation of Kinetex textile composite flooring modules is required.

2.04 ACCESSORIES

A. Kinetex requires protective transition 3/16-inch to other floor covering thickness. Provide transition/reducing strips tapered to meet abutting materials as indicated in the drawings.

B. Provide aluminum edge with lip to protect Kinetex edge.

PART 3 EXECUTION

3.01 INSPECTION

A. Examine and verify that sub-floor surfaces are smooth and flat within tolerances specified for that type of work and are ready to receive installation of modules.

- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive installation of modules.
- C. Verify that sub-floor surfaces are dust-free and free of substances that could impair bonding of adhesive materials to sub-floor surfaces.
- D. Verify that concrete sub-floor surfaces are dry enough and ready for flooring installation by testing for moisture emission rate and alkalinity in accordance with ASTM F 710; obtain instructions if test results are not within limits recommended by J+J Flooring.
- E. Verify that required floor-mounted utilities are in correct location.
- F. J+J Flooring requires that Kinetex textile composite flooring be inspected prior to installation for proper style, color and potential defects. No claims will be honored if the modules are installed with visible defects. Should there be a problem, call J+J Flooring's Customer Relations Department at 800.241.4586.

3.02 PREPARATION

- A. Starting installation constitutes acceptance of sub-floor conditions.
- B. **SURFACE PREPARATION-** Dust, dirt, debris and non-compatible adhesive must be removed before the installation begins. Surfaces must be smooth and level with all holes and cracks filled with Portland cement-based patch reinforced with polymers. Kinetex Adhesive cannot be applied to any substrate where chemical or solvent-based cleaners have been used.
- C. **LATEX ADHESIVES** - Old latex adhesives must be mechanically scraped down to a bare residue. Latex adhesive residues must be smooth and level with all holes and cracks filled with a Portland cement-based patch reinforced with polymers, or encapsulated with APAC ENCapSeal.
Note: Failure to remove or seal, old latex adhesive may cause installation failure, shifting, buckling or edge curling; these conditions will not be covered under warranty.
- D. **CUT BACK ADHESIVES** - Must be wet mechanically scraped to a minimum residue and encapsulated with APAC ENCapSeal.
Note: Failure to remove or seal old cut back adhesive may cause installation failure, shifting, buckling or edge curling; these conditions will not be covered under warranty.
- E. **CONCRETE MOISTURE TESTING and pH TESTING** - Substrate moisture testing is not required as Kinetex Modular Flooring using required Kinetex Adhesive is rated. up to 100% RH. Alkalinity tests should be performed per ASTM F 710. The maximum acceptable pH is 12. If reading is above 12, consult with the Customer Relations Team for the best resolution.

SUBFLOORS

- F. **New Concrete** - New concrete must be fully cured and free of moisture (see ASTM F 710). New concrete requires a curing period of approximately 90 days.
- G. **Old Concrete** - Old concrete must be checked for moisture. Dry, dusty, porous floors must be primed.
Note: Primers will not correct a moisture problem. For complete information, refer to CRI-104 Installation Standard.
- H. **Wood** - Wood floors must be APA flooring grade smooth and level, or CanPly Select Grade. If the floor is uneven, an approved underlayment will be required. Old finishes must be tested for compatibility with adhesives or removed and porous wood primed. Wood floors must receive a roll-on application of Commercialon® Premium Sealer. Follow instructions on the Commercialon® Premium Sealer label.

I. Terrazzo / Marble - Level all grout lines with Portland cement-based patch reinforced with polymers. Glossy surfaces must be sanded for proper adhesive bond. Waxes and similar finishes must be removed.

J. Other Hard Surfaces (VCT/VAT) - Tiles must be well secured to the floor or removed. Broken, damaged or loose tiles must be replaced. Waxes and similar finishes must be removed from VCT before applying adhesive. Existing sheet vinyl is not a suitable substrate for modular installation and must be removed.

K. Raised Access Panel Floors - The panels must be flat, warped panels can result in the carpet modules being off grid. The panel joints must be tight and level. Screws are to be countersunk. Kinetex is not recommended for installation over Raised Access Panel Floors if the panels are frequently accessed.

L. Gypcrete - Gypcrete subfloors must be fully cured and free of high moisture (see ASTM F 2170-2). Gypcrete requires a curing period of approximately 90 days. Additionally, Gypcrete must be treated using primer in advance of applying adhesive.

M. Carpet - Remove old carpet and carpet adhesives by scraping or other mechanical means. Any remaining adhesive residues may be covered with a Portland based patching compound or encapsulated with TriSeal Sealer.

3.03 INSTALLATION OF TEXTILE COMPOSITE FLOORING

A. Install flooring in strict accordance with the finish drawings and J+J Flooring's Kinetex installation instructions.

B. ADHESIVE SYSTEM - Kinetex requires use of Kinetex Adhesive for all Kinetex flooring modules installs.

1. Full Spread Kinetex Adhesive System: Installation requires full spread use of Kinetex Adhesive. The spread rate for Kinetex Adhesive is approximately 640 square feet per four- gallon bucket over a properly prepared floor and must be spread using a 1/16" x 1/16" x 1/16" square notched trowel. Kinetex adhesive is a transitional hard-set PSA with limited working time. Allow the adhesive to dry until the anchor lines are visible and begin installation. Once the control lines are visible complete the installation within 2 hours, which includes trimming and rolling. Replace the trowel clip each time that a new 4-gallon pail of Kinetex Adhesive is opened. Kinetex adhesive average coverage is 640 SF per 4 gallon pail or 160 SF per one gallon pail.

Note: Inadequate amounts of adhesive can cause modules to shift and move and will not be covered by warranty. J+J Flooring will not be responsible for the adhesive bond where other adhesives have been used.

C. MODULE PLACEMENT - Arrows are printed on the module backing to show pile/machine direction. A tight installation without compression is mandatory for optimum performance and appearance of the modular installation. It is critical that each module uniformly touch each adjoining module without a gap. To ensure a clean tight fit, do not pull/tug or slid-in modules, but instead lay each module into its location against the adjoining module. Use your hands to press/form the module into place where the new module meets the previously installed module. **See specific product specifications for approved installation method(s).**

Note: To reposition a Kinetex module during installation, remove it by gently lifting all four sides of the module with a spatula or putty knife, rotating around each side of the module doing a little at a time. The very center of the module should be the last part of the module touching the floor upon removal. Do not stretch a module while it is in the adhesive in order to align next to an adjoin modular. An attempt to stretch will likely result in the module pulling back to its original position. NEVER ATTEMPT TO

REMOVE A MODULE ALL AT ONCE BY PULLING ONE OR ONLY TWO SIDES OF THE MODULAR. DOING SO MAY LEAD TO DISTORTING THE MODULE.

D. **PALLET AND BUNDLE SEQUENCING** - It is very important to install Kinetex modules in the order they were manufactured; this is easily accomplished by selecting pallets in sequential order and following the numbers located on each bundle of modules. Typically, an installation will begin with the lowest bundle numbers and progress through the highest numbers until the project is complete. Installing modules by bundle sequence will assure the most even uniform look possible. (For layout and installation instructions refer to J+J Flooring's Kinetex Installation Instructions.)

E. **STAIRS** - Use single or double undercut stair nosing and cut modules. Then, using full spread Kinetex Adhesive or SRT Tape, install modules on steps and risers, inserting the stair nosing edge and the top of the riser edge of each module into the vinyl undercut.

F. **COMPLETING INSTALLATION** - To avoid dislodging modules, do not walk on or move furniture onto modules until the area is completely anchored. Roll entire area with 75-100 lb. roller in both directions (north-south and east-west) after completion of installation. It is also required that sheets of plywood or hardboard be laid over the new modular surface when transporting heavy furniture on carts or dollies. As a final step, vacuum the entire area with an upright vacuum.

3.04 INSTALLATION OF ACCESSORIES

A. Install accessories as required by drawings and per manufacturer's specifications.

3.05 CLEANING AND PROTECTION

A. Use a moist cloth when wet; if dry, use a solvent based product applied to a towel then worked onto the Kinetex module for removal of contaminants such as adhesive, paint, oil and grease. Follow J+J Flooring's maintenance guidelines.

B. Clean and vacuum surfaces.